(*i*) Neither the lessee nor his employees shall enter the forest either before sunrise or after sunset.

(*j*) The lessee shall soon after the sale is confirmed, deposit of Rs. 100 (one hundred only) as security for the due fulfilment of the conditions of the lease. In the event of the breach of any of the above conditions, the money deposited as security shall be forfeited to Government in whole or in parts as the Conservator of Forests may decide and the lease liable to be cancelled.

6. The sale does not prohibit the issue of retail licenses at seigniorage rates or the exercise of the rights of the villagers.

Abstract Notification dated 10th August 1929.

The attention of the public is invited to the undermentioned sale notifications of this Division published in pages 861-864, Part VI of the *Mysore Gazette*, dated 15th August 1929.

1. Sale of Tupra leaves for three years from 1929-30.
2. Sale of Honge leaves and seeds for 1929-30.
3. Sale of canes for 1929-30.

S. VENKATAVARADIENGAR,
District Forest Officer.

ENGINEERING DEPARTMENT.

BANGALORE DIVISION.

Abstract Notification.

The attention of the public is invited to the detailed notice inviting quotations for "Insuring the Government Press Buildings with all the Machinery and Fittings at Bangalore against fire" published on page 832 of Part VI of the *Mysore Gazette*, dated 8th August 1929.

2. The last date for receiving the quotations is 2 P.M. of 25th August 1929.

H. R. VENKATASUBBA RAO,
Executive Engineer.

KOLAR DIVISION.

Notification dated 15th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Kolar Division,up to 2 P.M., of 9th September 1929, for restoring Jodi Mallenahalli Tank, Goribidnur Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of April 1930.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar, between the hours of 11 to 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred in Cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Jodi Mallenahalli Tank, Goribidnur Taluk", in default of which tenders will be rejected.

5. The final acceptance of any tender will rest with the Executive Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. The tenderers must quote specific rates for each item of work both in words and in figures.

10. The tenderer stating that the work would be executed at a certain percentage in excess or lower than the estimate will not be accepted.

Abstract estimate for restoring Jodi Mallenahalli Tank of Giribidnur Taluk :—

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		
1	Earthwork to bund including watering and tamping.	C.yds.		2,683	
2	Turfing to bund	Sq.yds.		2,614	
3	Resetting old stone with new jelly ...	C.yds.		974	
4	New stone work	,,		929	
5	Fixing new grade stones including figuring and painting.	No.		24	
6	Fixing new index stones	,,		24	
7	Do Register No. stone including figuring and painting.	,,		1	
8	Do do B. M. stones ...	,,		2	
9	Do do Gauge stone ...	,,		1	
10	Clearing jungle	Grade		14	
	Total Bund ...	...	...	...	...
	Sluice at R. L. 44·00.				
1	Earthwork excavation	C.yds.		72	
2	Refilling the same	,,		53	
3	Concrete in surky mortar	C.ft.		225	
4	Burnt brick in surki mortar	,,		825	
5	Burnt stone slabs 6" thick	S.ft.		238	
6	Surki mortar plastering	Sqr.		6·13	
7	Providing plug and rod with locking arrangement.	L. S.		..	
8	Cutting holes for orifice and crass and vent way slabs.	No.		4	
	Total sluice ...	...	...	...	...
	Waste weir.				
1	Earthwork excavation	C.yds.		236	
2	Surki concrete	C.ft.		624	
3	Burnt brick in surki mortar	,,		14·83	
4	Surki mortar plastering	Sqr.		20·76	
5	Burnt stone slabs 6" thick	S.ft.		816	
6	Removing and resetting old stone with new jelly.	C.yds.		220	
7	Tongue and groove joints	No.		23	
	Total Contingencies ...	...	...	...	...
	Grand Total ...	...	...	...	...

Notice dated 4th August 1929.

The attention of the public is invited to the Notification published in the *Mysore Gazette*, Part VI, page 829, dated 8th August 1929, calling for tenders for Providing Stone Slab parapet on Lakshmisagara Tank Bund on Mulbagal-Goribidnur Road, Mulbagal Taluk. The last date of tender is 27th August 1929.

N. LAKSHMINARASIMHAIYA,
Executive Engineer.

MYSORE DIVISION.

Notice dated 14th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 9th September 1929, for Restoring Begamangala-Nagankere, Nagamangala Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1931.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore Division, between the hours of 11 A.M. and 5 P.M., on working days.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred only in cash or Government Promissory Notes, as earnest money and be superscribed "Tender for Restoring Begamangala Nagankere, Nagamangala Taluk, in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond, in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted will be posted on the notice board in the Executive Engineer's Office, in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

9. Rates should be quoted for each item of work.

10. Wherever L. S. or noted the tender should also be for similar sums.

Abstract estimate for Restoring Begamangala-Nagankere, Nagamangala Taluk.

No.	Items of work	Unit	Rate	Quantity	Cost
	Bund.		Rs. a. p.		Rs.
1	Clearing jungle over bund		Lump sum		
2	Clearing grass, etc., on old bund and cutting steps and grips for new earthwork.		Do		
3	Earthwork to bund with watering and tamping, etc., complete.	C.yd.		5,064	
4	Earthwork available from right waste weir approach and draft clearing with lead and consolidation.	,,		7,708	
5	Turfing to slopes	Sqr.		517·15	
6	Gravel backing to revetment	C.yd.		757	
7	Rough stone work for revetment with jelly backing	,,		2,225	
8	Providing grade stones including cutting figures and painting, etc., complete.	each		23	
9	Providing index stones	,,		23	
10	Providing guage stone including cutting figures and painting.	,,		1	
11	Providing register number and date stone including cutting figures and painting, etc.	,,		1	
12	Providing bench mark stone, etc., complete ...	,,		2	
	Breach.				
1	Clearing sand and silt in breach	C.yd.		1,778	
2	Earthwork excavation foundation	,,		400	
3	Benching rock	S.ft.		188	
4	Cutting steps and grips for earthwork to bund, etc., in breach portion.		Lump sum		
5	Earthwork to bund with watering and tamping, etc., complete.	C.yd.		14,414	
6	Puddle wall including watering and ramming ...	,,		1,747	
7	Burnt brick in surki mortar	C.ft.		1,125	
8	Rough plastering with surki mortar	Sqr.		17·06	
9	Gravel backing to revetment	C.yd.		314	
10	Rough stone work with jelly packing... ...	,,		751	
11	Turfing to slopes of bund	Sqr.		186·35	

No.	Items of work	Unit	Rate	Quantity	Cost
	Constructing 2 masonry sluices—Details for one sluice.		Rs. a. p.		Rs.
1	Earthwork for cutting and opening the bund for sluice work.	C.yd.		193	
2	Stone jelly concrete in surki mortar	C.ft.		449	
3	Burnt brick in surki mortar	,,		753	
4	Burnt stone slabs dressed and fixed	S.ft.		232	
5	Plastering with surki mortar	Sqr.		8·00	
6	Earthwork filling the opening with watering and tamping, etc.	C.yd.		193	
7	Cutting holes in orifices and guide and gibbet slabs	each		4	
8	Providing wooden plug with iron rod and locking arrangements.		Lump sum		
	Constructing right waste weir 200 feet long.				
1	Earthwork excavation, foundation and making use the earth for training bank with watering, etc., complete.	C.yd.		463	
2	Jelly concrete in surki mortar	C.ft.		684	
3	Burnt brick in surki mortar	,,		1,143	
4	Plastering in surki mortar	Sqr.		17·35	
5	Burnt stone slabs 6 inches thick dressed and fixed	S.ft.		586	
6	Rough stone work with jelly packing ...	C.yd.		132	
7	Earthwork excavation approach and draft clearing	,,		7,708	

N. G. KRISHNA IYENGAR,
Executive Engineer.

SANITARY AND TOWN PLANNING DIVISION.

Dated 15th August 1929.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Sanitary and Town Planning Division, up to 12 noon on 6th September 1929, for the supply of sanitary fittings and galvanized iron pipes and fittings required for "Providing Sanitary Fittings to Mr. Munivenkatappa's Wards at the Tuberculosis Sanatorium Hospital, Mysore, and for the New Operation Theatre of Vani Vilas Hospital, Mysore". An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of 15th October 1929.

2. Tenders should be submitted on printed forms, which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed,

3. Each tender must be accompanied by a deposit of Rs. 50 in Cash or Government Promissory Notes, as earnest money and be superscribed "Tender for the supply of sanitary Fittings and Galvanized Iron Pipes", in default of which tenders will be rejected.

4. The final acceptance of any tender will rest with the Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

5. Within eight days of acceptance of the tender, the successful competitor will be required to execute the usual contract bond in default of which his tender will be considered cancelled, and his earnest money will be forfeited.

6. The name of the successful competitor, whose tender has been accepted, will be posted on the Notice Board in the Executive Engineer's Office, in due course. No. enquiries regarding the acceptance or rejection of a tender will receive any reply.

7. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

8. In all matters of disputes not specially provided for and in all matters of disputes about rates, quantities, measurements and quality of work and in all disputes of any kind, the decision of the Chief Engineer, will be final and legally binding.